

ORDER BY COUNTY HIGHWAY COMMITTEE
FOR
RELOCATION AND ACQUISITION OR RIGHTS-OF-WAY
ON
COUNTY TRUNK HIGHWAY

Grant County, Project No. 5957-3-00, C.T.H. "U"

WHEREAS, the County Highway Committee of Grant County finds that the proper improvement or maintenance of a 2000.00 foot portion of the above County Aid Highway in the Town of Potosi, Grant County, from a point:

Beginning at a point 56.03 feet East and 707.59 feet North of the Southwest Corner of Section 21, Town 3 North, Range 3 West, Town of Potosi, said point being the beginning of the relocation order and being at the centerline of the existing County Trunk Highway "U" and also being known as Station 114+00; thence N32°23'W for 466.15 feet to a point of curvature to the left; thence Westerly 763.03 feet along the arc of a curve with a radius of 1041.74 feet to a point of tangency; thence N74°21'W for 370.82 feet to a point; thence N74°51'W for 400 feet to a point also known as Station 134+00, said point being at the centerline of the existing County Trunk Highway "U" and being 1751.00 feet North and 1535.53 feet West of the said Southwest Corner of said Section 21, said point also being the end of the relocation order;

requires certain relocations or changes, and the acquisition of certain Rights-of-Way as shown on the attached plat marked Plat of Right-of-Way Required For Potosi - C.T.H. "N" Road, Boice Creek Bridge and Approaches, C.T.H. "U", Grant County, dated September, 1985.

IT IS HEREBY ORDERED, under authority granted by Section 83.08, Wisconsin Statutes, that said Highway be and is hereby changed or re-located and that Rights-of-Way be acquired in accordance with said plat.

ORDERED by the County Highway Committee of the County of Grant and entered in the minutes of its meeting on MAY 13 - 1986.

Clarence J. Schauff
Edward J. Splinter
Ralph L. Noble
W. Lee Ties
Silbert Wood
Highway Committee Members

ALL COORDINATES SHOWN ON THIS PLAT ARE BASED ON THE WISCONSIN COORDINATE SYSTEM, SOUTH ZONE, AND ARE SCALED FROM U.S.G.S. TOPOGRAPHIC MAP POTOSI WISCONSIN QUADRANGLE FOR IDENTIFICATION ONLY.

AREAS SHOWN IN THE SCHEDULE OF LANDS AND INTERESTS
TABLE UNDER TOTAL ACRES MAY BE APPROXIMATE AND
ARE DERIVED FROM TAX ROLLS AND OTHER AVAILABLE
SOURCES AND MAY NOT INCLUDE LANDS OF THE OWNER
WHICH ARE NOT CONTIGUOUS TO THE AREAS TO BE
ACQUIRED.

SCHEDULE OF LANDS & INTERESTS REQUIRED

PARCEL NUMBER	SHEET NUMBER	OWNER	INTEREST REQUIRED	L.H.E. ACRES		R/W ACRES		REQ'D	TOTAL ACRES REM.	OPERATION PROJECT I.D.
				TEMP.	PERM.	NEW	EXIST.	TOTAL		
1	1	LAVERNE O. & JOYCE E. LOLWING	FEE	—	—	0.29	0.61	0.90	158.10	
2	1	VALENA EHLEN	FEE	—	—	0.61	1.38	1.99	49.5	
3	1	DAVID & JOAN EDGE, VENDEE RAY EDGE, VENDOR	FEE	—	—	0.32	0.81	1.13	78.87	
4	1	CLARENCE J. & DOROTHY REYNOLDS	FEE	—	—	0.32	1.65	1.97	387.5	

REVISION DATE	R/W PROJECT NUMBER 5957-03-00	SHEET NUMBER
MARCH 10, 1986	FEDERAL PROJECT NUMBER	
MARCH 20, 1986	PLAT OF RIGHT OF WAY REQUIRED FOR POTOSI - C.T.H. "N" ROAD BOICE CREEK BRIDGE & APPROACHES C.T.H. "U", GRANT COUNTY 0 100 200 DATE <u>SEPT. 1985</u>	
	CONSTRUCTION PROJECT NUMBER	5957-3-71

CURVE DATA

R/W CURVE 1

$$\begin{aligned}\Delta &= 41^{\circ} 58' \\ D^{\circ} &= 5^{\circ} 30' \\ T &= 399.54' \\ L &= 763.03' \\ R &= 1041.74' \\ P.C. &= 118+66.15 \\ P.T. &= 126+29.18 \\ S.E. &= 0.074 \frac{1}{2}\end{aligned}$$

L.C. = 399.56'
L.C.B. = N. 62° 33' W.
R. = 976.74'
L. = 402.40'

① LAVERNE O. LOLWING &
JOYCE F. LOLWING

④ REYNOLDS

BEGIN RELOCATION ORDER PROJECT 5957-03-00
STA. 114+00

LOCATED 56.03' EAST AND 707.59' NORTH
OF THE S.W. CORNER OF SEC. 21, T.3N., R.3W.

N=260,760'±200'
E=1,800,840'±200'

END RELOCATION ORDER PROJECT 5957-03-00
STA. 134+00

LOCATED 1751.00' NORTH AND 1,535.53' WEST
OF THE S.W. CORNER OF SEC. 21, T.3N., R.3W.

$$N = 261,800' = 200'$$

$$E = 1,799,260' \pm 200'$$

APPROVED FOR
GRANT COUNTY
BY

Mar. 13 - 1986
DATE

MAR. 13 - 1984
DATE

Nelson J. Grake
OFFICIAL

PLAT PREPARED BY
GRANT COUNTY HIGHWAY DEPT.
LANCASTER, WISCONSIN