

RELOCATION ORDER
by
COUNTY HIGHWAY COMMITTEE, GRANT COUNTY
for
RELOCATION AND ACQUISITION OF RIGHT-OF-WAY
on
WYALUSING - CTH "CX" ROAD
COUNTY TRUNK HIGHWAY "X"
GRANT COUNTY

WHEREAS, the County Highway Committee finds that proper establishment, laying out, constructing, improving, and maintaining a 17566.98 foot portion of County Trunk Highway "X" and described as follows:

Beginning at a point located 1391.35 feet north of and 226.16 feet west of the southeast corner of Section 36, Town 6 North, Range 7 West, Town of Wyalusing, Grant County, Wisconsin, said point being located on the centerline of County Trunk Highway "X" at a point referred to as Station 13+75 approximately 125.0 feet south of the "Dana Branch" creek; Thence 750.00 feet along the arc of a curve to the right having a radius of 2291.83 feet which is subtended by a chord bearing N 21-06'-30" E, 746.66 feet; Thence N 30-29'-00" E, 865.63 feet; Thence 354.76 feet along the arc of a curve to the right having a radius of 818.51 feet which is subtended by a chord bearing N 42-54'-00" E, 351.99 feet; Thence N 55-19'-00" E, 353.15 feet; Thence 551.43 feet along the arc of a 818.51 foot radius curve to the left which is subtended by a chord bearing N 36-01'-00" E, 541.06 feet; Thence N 16-43'-00" E, 207.46 feet; Thence 468.57 feet along the arc of a 818.51 foot radius curve to the right which is subtended by a chord bearing N 33-07'-00" E, 462.20 feet; Thence N 49-31'-00" E, 1200.91 feet; Thence 169.76 feet along the arc of a 818.51 foot radius curve to the left which is subtended by a chord bearing N 43-34'-30" E, 169.46 feet; Thence N 37-38'-00" E, 819.80 feet; Thence 212.81 feet along the arc of a 818.51 foot radius curve to the right which is subtended by a chord bearing N 45-04'-54" E, 212.21 feet; Thence N 52-31'-49" E, 670.04 feet; Thence 135.67 feet along the arc of a 818.51 foot radius curve to the left which is subtended by a chord bearing N 47-46'-55" E, 135.52 feet; Thence N 43-02'-00" E, 1448.16 feet; Thence 237.47 feet along the arc of a 1432.39 foot radius curve to the right which is subtended by a chord bearing N 47-46'-58" E, 237.20 feet; Thence N 52-31'-56" E, 1457.74 feet; Thence

[illegible]