

RELOCATION ORDER  
By  
WATERLOO TOWN BOARD, GRANT COUNTY  
For  
RELOCATION AND ACQUISITION OF RIGHT-OF-WAY  
On  
TOWN HIGHWAY, CHAFFIE HOLLOW ROAD

WHEREAS, the Town Board of Waterloo Township finds that proper establishment, layint out, construction, improving, and maintaining a 1,300.00 foot portion of Town Highway known as Chaffie Hollow Road and described as follows:

Beginning at a point 1,936.10 feet south and 2,441.63 feet west of the north-east corner of Section 21, Township 3 north, range 4 west, said point being located on the centerline of Chaffie Hollow Road at station 12+00.00 thence N 52°44'02"E, 65.53 feet to a point of curvature of a 1909.86 foot radius curve to the right; thence along the arc of said curve 268.50 feet, whose long chord bears N 56°45'41" E, 268.28 feet to a point of tangency; thence N 60°47'20" E, 667.74 feet to a point of curvature of a 1909.86 foot radius curve to the left; thence along the arc of said curve 158.33 feet, whose long chord bears N 58°24'50" E, 158.29 feet to a point of tangency; thence N 56°02'20" E, 139.90 feet to a point on the centerline of Chaffie Hollow Road at Station 25+00.00, said point being located 1,262.44 feet south and 1,331.40 feet west of the north-east corner of Section 21.

AND WHEREAS, the Town Board of Waterloo Township finds that removing, obliterating, and vacating a 931.41 foot portion of Town Highway known as Chaffie Hollow Road, following construction of the new highway and bridge, and described as follows:

Beginning at a point 1,327.13 feet south of and 1,427.45 feet west of the north-east corner of Section 21, Township 3 north, range 4 west, said point being located on Chaffie Hollow Road at Station 24"TL"+31.41; thence S 41°04'33" W, 434.91 feet; thence S 76°49'02" W, 496.50 feet, to a point, said described line being located across a 50 foot pony truss and an adjoining 125 foot high steel truss bridge both of which are to be removed, said point being located on the centerline of Chaffie Hollow Road at Station 15"TL"+00.00, said point being located 1,768.21 feet south of and 2,186.63 feet west of the north-east corner of Section 21.

Requires certain relocation or changes and the acquisition of lands or interests in lands as shown on the attached plat marked "plat of right-of-way required for Chaffie Hollow Road Bridge and Approaches, Town of Waterloo, Grant County, Project I.D. \_\_\_\_\_ dated 6-9-81.

IT IS HEREBY ORDERED, under authority granted by section 60.29, Wisconsin Statutes, that said Town Highway be and is hereby changed or relocated, and that right-of-way be acquired in accordance with said plat.

Ordered by the Waterloo Town Board, Grant County, and entered into its minutes on July 7-1981.

Joseph O Esser  
Joseph Esser, Chairman

Carol J. Weber  
Carol Weber, Clerk

Joe Grosser  
Joe Grosser, Supervisor

Maurice Wamsley  
Maurice Wamsley, Supervisor

Lois Reed  
Lois Reed, Treasurer

RIGHT-OF-WAY ACQUISITION DESCRIPTION

Fee title in and to the following tract of land owned by Myra Eckstein, described as a parcel of land in Section 21, T3N, R4W, Township of Waterloo, Grant County, Wisconsin. Said parcel includes all of the land of the Grantor contained in the following traverse:

Commencing at the north-east corner of Section 21, Township 3 north, range 4 west, Township of Waterloo, Grant County, Wisconsin; thence S 46°31'23" W, 1,834.77 feet to a point located on the centerline of Chaffie Hollow Road and the point of beginning; thence S 33°57'40" E, 33.00 feet; thence S 56°02'20" W, 139.90 feet to a point of curvature of a 1,942.86 foot radius curve to the right; thence along the arc of said curve 161.07 feet, whose long chord bears S 58°24'50" W, 161.02 feet to a point of tangency; thence S 53°27'53" W to and through the easterly bank of the Grant River 329.46 feet; thence S 67°48'40" W to and through the westerly bank of said Grant River 343.55 feet, to a point of curvature of a 1,876.86 foot radius curve to the left; thence along the arc of said curve 263.86 feet, whose long chord bears S 56°45'41" W, 263.64 feet to a point of tangency; thence S 52°44'02" W, 65.53 feet; thence N 37°15'58" W, 66.00 feet; thence N 48°54'17" E, 463.01 feet; thence N 60°47'20" E, to and through the westerly bank of the Grant River, 150.00 feet; thence N 70°15'23" E, to and through the easterly bank of said Grant River, 407.32 feet, to a point of curvature of a 1,876.86 foot radius curve to the left; thence along the arc of said curve 155.60 feet, whose long chord bears N 58°24'50" E, 155.55 feet, to a point of tangency; thence N 56°02'20" E, 139.90 feet; thence S 33°57'40" E, 33.00 feet to the beginning.

Said parcel contains 3.0 acres more or less, which includes 1.8 acres of new Right-of-Way and 1.2 acres, more or less, of existing Right-of-Way.

Subject to all other easements and restrictions of record.

Grantor: Myra Eckstein

Grantee: Township of Waterloo, Grant County

Description by: Ronald J. Brys, Donohue & Associates, Inc.

Project No.: Chaffie Hollow Road Bridge & Approaches

Parcel: 1