



PLAT OF SURVEY for DOUG AND KARLA WOLF



Bearings referenced to the West line of the NW 1/4 of Section 3 which is assumed to bear N 00°30'40" W.

50 0 50 100
SCALE 1" = 50'

All plans that do not show a seal imprint in red ink may contain unauthorized alterations. The certification contained on this document shall not apply to any copies. Dated this 15th day of February, 2000.



PARK ROAD

- LEGEND**
- Section corner - as designated
 - Set No. 6 x 24" rebar with cap
 - Existing No. 6 rebar
 - △ Existing 1" iron pipe
 - Existing 2" iron pipe
 - *-*-* Existing fence
 - () Recorded as

B L O C K A s s e s s m e n t P l a t C i t y o f L a n c a s t e r

Lot 4

Lot 3

Lot 5

Lot 2

Lot 1

STREET

ELM

Southwest corner, Section 34, T5N R3W, 4th P.M., Grant County, Wisconsin, Existing 2" dia. iron pipe

Northwest corner, Section 3, T4N R3W, 4th P.M., Grant County, Wisconsin, Existing Stone monument

West 1/4 corner, Section 3, T4N R3W, 4th P.M., Grant County, Wisconsin, Existing 7/8" dia. rebar

0.40 ACRES ±
17,554 SQ. FT. ±

Point of Beginning

AUSTIN ENGINEERING, LLC
4211 HWY 81 E, LANCASTER, WI 53813
PHONE 608-723-6363 FAX 608-723-6702

FIELDBOOK: 9917
G: \T4NR3W\04
C: \SC14\WORK\LANCSTER\AP\B8DW

DRAWN BY: AJ AUSTIN
APPROVED: LL AUSTIN
CREW: BS - SB

PLAT OF SURVEY for DOUG AND KARLA WOLF

DESCRIPTION:

A parcel of land located in the Southwest Quarter (SW 1/4) of the Northwest Quarter (NW 1/4) of Section Three (3), Township Four (4) North, Range Three (3) West of the 4th P.M., Grant County, Wisconsin, said parcel being described as follows:

Commencing at the West Quarter (W 1/4) corner of said Section Three (3);
Thence North 00° 30' 40" West 60.00' along the West line of said Section Three (3);
Thence South 89° 48' 05" East 132.00' along the North line of Elm Street to a no. 6 rebar marking the point of beginning;
Thence South 89° 48' 05" East 132.00' along the North line of Elm Street to a no. 6 rebar;
Thence North 00° 30' 40" West 133.00' to a no. 6 rebar;
Thence North 89° 48' 05" West 132.00' to a no. 6 rebar;
Thence South 00° 30' 40" East 133.00' to the point of beginning, containing 0.40 acres, more or less, and being subject to any and all easements of record and/or usage.

Also shown by Assessment Plat of the City of Lancaster, Grant County Wisconsin, recorded in the Office of the Register of Deeds for Grant County Wisconsin, in Volume 1 of Plats on Page 34, as part of Lot Two (2), Block Eight (8), Assessment Plat.

SURVEYOR'S CERTIFICATE:

I, Larry L. Austin, Registered Wisconsin Land Surveyor, hereby certify:

That the above description was surveyed, mapped and monumented as shown on this plat by me or under my direct supervision.

That conformance with local ordinances are not guaranteed with this survey.

That this survey was prepared under the direction of Doug and Karla Wolf.

That to the best of my knowledge and belief, this plat is an accurate representation thereof.

That all plans that do not show a seal imprint in red ink may contain unauthorized alterations.

The certification contained on this document shall not apply to any copies.

Dated this 15th day of February, 2000.


Larry L. Austin, S-1903


AUSTIN ENGINEERING, LLC

4211 HWY 81 E, LANCASTER, WI 53813
PHONE 608-723-6363 FAX 608-723-6702

FIELDBOOK: 9917

G:\T4NR3W\04

C:\SC14\WORK\LANCASTER\AP\B8DW

DRAWN BY: AJ AUSTIN

APPROVED: LL AUSTIN

CREW: BS - SB

SHEET 2 OF 2