

PLAT OF SURVEY for JOHN SCOTT and TOM FLOYD

LOCATED IN THE NE 1/4-NE 1/4, SE 1/4-NE 1/4, SW 1/4-NE 1/4, NW 1/4-NE 1/4 AND THE NW 1/4-SE 1/4 OF SECTION 32 AND THE NW 1/4-NW 1/4 OF SECTION 33, T6N R6W, WYALUSING TOWNSHIP, GRANT COUNTY, WISCONSIN



DESCRIPTION OF PARCEL "A" - JOHN SCOTT PARCEL:

Description provided:
THE NORTHWEST QUARTER OF THE NORTHEAST QUARTER (NW 1/4-NE 1/4); THE SOUTHWEST QUARTER OF THE NORTHEAST QUARTER (SW 1/4-NE 1/4) EXCEPT THAT PART OF SAID FORTY LYING WEST OF BURROWS HILL LANE AND; THAT PART OF THE NORTHWEST QUARTER OF THE SOUTHEAST QUARTER (NW 1/4-SE 1/4) LYING EAST OF BURROWS HILL LANE AND NORTH OF GASNER HOLLOW ROAD; ALL IN SECTION THIRTY-TWO (32) IN TOWNSHIP SIX (6) NORTH, RANGE SIX (6) WEST, GRANT COUNTY, WISCONSIN.

DESCRIPTION OF PARCEL "B" - THOMAS FLOYD PARCEL:

Description provided:
The East Half (E 1/2) of the Northeast Quarter (NE 1/4) of Section Thirty-two (32), Township Six (6) North of Range Six (6) West of the 4th P.M., Grant County, Wisconsin, EXCEPT that part of said East Half (E 1/2) of the Northeast Quarter (NE 1/4) lying South of Gasner Hollow Road. And all that part of the Northwest Quarter of the Northwest Quarter (NW 1/4-NW 1/4) of Section Thirty-three (33) in Township Six (6) North of Range Six (6) West of the 4th P.M., Grant County, Wisconsin, lying West of Gasner Hollow Road.

SURVEYOR'S CERTIFICATE:

I, Larry L. Austin, Registered Wisconsin Land Surveyor, hereby certify:
That the above descriptions were surveyed, mapped and monumented as shown on this plat by me or under my direct supervision.
That this survey was prepared under the instructions of John Scott and Thomas Floyd.
That to the best of my knowledge and belief, this plat is an accurate representation thereof.
That all plans that do not show a seal imprint in red ink may contain unauthorized alterations.
The certification contained on this document shall not apply to any copies.

Dated this 18th day of May, 2001.

Larry L. Austin, S-1903
SURVEYOR

CURVE DATA

CURVE	ARC LENGTH	RADIUS	CHORD BEARING	CHORD LENGTH
C1	80.35	800.00	S 74°23'10" W	80.32
C2	294.35	1000.00	S 68°49'51" W	293.29
C3	244.14	800.00	S 69°08'27" W	243.19
C4	143.23	100.00	N 61°05'04" W	131.30
C5	234.52	575.00	N 09°22'03" W	232.90
C6	178.72	250.00	N 17°09'47" W	174.94
C7	149.02	500.00	N 46°10'53" W	148.47
C8	249.13	800.00	N 62°35'15" E	248.13
C9	150.29	400.00	N 64°25'48" E	149.41
C10	214.10	225.00	N 47°56'02" E	206.11
C11	370.30	875.00	N 32°47'53" E	367.54
C12	414.79	4500.00	N 47°33'45" E	414.64
C13	358.22	275.00	N 12°53'34" E	333.43
C14	181.47	1100.00	N 19°41'56" W	181.26

AREA TABLE

PARCEL "A"

SECTION 32
NW-NE = 40.07 ACRES±
SW-NE = 36.37 ACRES±
NW-SE = 2.01 ACRES±

PARCEL "B"

SECTION 32
NE-NE = 39.98 ACRES±
SE-NE = 23.34 ACRES±
SECTION 33
NW-NW = 7.55 ACRES±

LEGEND

- ⊕ No. 8 rebar found with Grant County Aluminum Cap
- ⊙ No. 8 x 30" rebar set with Grant County Aluminum Cap - wt=2.67#/l.f.
- No. 6 rebar found
- No. 6 x 24" rebar set with cap - wt=1.50 #/l.f.
- Wood lathe set
- ⊕ Railroad spike set
- + No monument set
- () Recorded as
- - - - - Approximate location of fence

0 300 600
SCALE 1" = 300'

PLAT OF SURVEY for JOHN SCOTT
LOCATED IN SECTION 32 AND SECTION 33, T6N R6W,
WYALUSING TOWNSHIP, GRANT COUNTY, WISCONSIN

AUSTIN ENGINEERING, LLC
421 HWY 81 E, LANCASTER, WI 53813
PHONE 608-723-6363 FAX 608-723-6702

FIELDBOOK: SDR33, 2042
C:\A\T6NR6W\32\35-SCOTT
DRAWN BY: AJ AUSTIN
APPROVED: LL AUSTIN
CREW: BS - SA - TF
SHEET 1 OF 1