

Survey of Section 14, T. 1 R. 2

Survey made for Horace Smoad in Section 14 of Town No. 18. of Range No. 2 West of the 4th. Principal Meridian N.P.

Preliminary Survey

Commencing at S.W. corner of said Section; thence East assumed Var. 8.40' E. 39.44/100 chs. ^{South} ~~South~~ of 1/4 Post between Sec. 14 and 23 - 124 Links. Corrected var. back li.

Commencing at said 1/4 Post, thence East, 39.36/100 chs. intersect Sec. line North of S.E. corner of said Sec. 14, 135 Links. Corrected variation back 6.44' E.

Commencing at 1/4 Post between Sec. 14 and 23 - thence North - assumed Var. 8.40' E. 79.41/100 chs. intersect Sec. line West of 1/4 Post between Sec. 14 and 107 Links. Corrected var. back 7.54' E.

Commencing at N.E. corner of said Sec. 14. Thence South - assumed Var. 8.30' E. 79.83/100 chs. intersect Sec. line East of S.E. cor of 14, 40 Links. Corrected variation back 8.12' E. Establish 1/4 Post between Sec. 13 and 14.

Commencing at 1/4 Post between Sec. 13 & 14 thence West - assumed Var. 8.15' E. 79.12/100 chs. intersect Sec. line South of 1/4 Post between Sec. 14 & 180 Links. Corrected var. back 6.58' E.

Distance of Center Posts apart 5 Links

146A

No. 256

Survey made for Horace Smoad of E. 1/4 of S.W. 1/4 of Sec. 14 Town No. 18. of Range No. 2 West, 4th. Principal Meridian N.P.

Commencing at 1/4 Post between Sec. 14 and 23 - it being the S.E. corner of

Said

39.70/100

Var. 6.5

South

B.O. 2

{ B.O. 1

14 and

Sec. 1

of 1/4
Princi

Sec. 1
S.E. 1/4

70/100

Var. 6.5

Thence

B.O. 1

{ No. 1

14 and

Sec. 1