

Survey made for Commissioners of Grand County Wisconsin Territory in the N. E. 1/4 of Section No. 14, Town No. 4 North of Range No. 3 West of the 4th Principal Meridian in said County. Commencing at the corner of Sections Nos. 10, 11, 12 & 13. Thence East, Mandoms on North side of said section - Variation 8⁵⁵' E.

At 40. Chains set Temporary quarter section post
 At 80.56 chains Intersect. 2 chains North of the section corner of Secs Nos. 11, 12, 13 & 14. West corrected. True bearing 40.28 Chains set quarter section post, which post with its bearings had been destroyed.

Then North on the East side of said section Variation 9³⁰' E

At 40 Chains set temporary quarter section post
 At 79.39 chains Intersect 84 links East of the corner of Sections Nos. 11, 12, 13 & 14. Corrected back True bearing 10⁰⁵' E

39.69^{1/2} Chains and set quarter section post, one of the original bearings of which had been destroyed and the true distance to the other had not been given.

South, Mandoms through the center of said section bearing 10⁰' E: at 79.96 Chains Intersect section line 6 links East of the quarter section post

Corrected back True bearing 9³⁴' E 39.98 chains and set temporary 1/4 post. East, Mandoms through the center bearing 8⁰' E 80.50 Chains Intersect sec line

2.8 links North of quarter section post. West corrected True bearing 7⁴⁸' E 40.28 Chains set quarter section post in the center of section

Thence North Variation 9³⁴' E five chains and set post. Thence East variation 7⁴⁸' E To a point in the section line on the East side of said section 5 chains North of the quarter section post. Cutting off

of the South side of the N. E. 1/4 of said section 20 & 1/10 Acres

Diagram and certificate on next page

18
 2/5
 12