

No 12

Field notes of Survey made by Charles Dickey for Christian Weatherall April 18th 1854 of NW 1/4 of SW 1/4, SE 1/4 of NW 1/4 of Section 21 Township one North Range 1 West

Commencing at quarter section corner on South side of said section ran thence North through said section. Then corrected South 40 chains. Then from quarter section corner on West side of said section ran East through said section. Then corrected and set stake for center of said section at 40 chains from East West and also at 40 chains from North and South boundaries thereof and at true intersection of said East West with said North and South line. Thence corrected West 20 chains and set stake for 1/8 section corner. Then retraced North boundary of SW 1/4 of said section and set post for 1/8 section corner at equal distances from the NW and NE corners of the same. Then retraced South boundary of SW quarter of said section and set stake for 1/8 section corner at equal distances from SW and SE corners of same. Thence ran North through center of SW 1/4 of said section to 1/8 section corner on North boundary thereof. Thence ran North through NW quarter of said section to 1/8 section corner on North boundary of same. Correct Variation of said Survey 9° 25' E

A true Record of Notes of said Survey.
Attest

Recorded May 1st 1854

Charles Dickey
Deputy County Surveyor

No 13

Survey made for Henrich Pellow by John G Clark County Surveyor by Solomon Goodrich Deputy of a five acre lot lying & being in the SE 1/4 of NE 1/4 of Section 13 Township 3 North of Range 3 West of 4th P.M. March 16th 1854

James Eddy and James Hewitt chainmen having been first duly sworn.

Commencing at SW corner of SE 1/4 of the NE 1/4 of said section ran thence North Variation 8° 15' East 10 chains and set temporary post. at 20 chains fell 22 links ^{East} of 1/8 section corner. Thence corrected South 10 chains and set Post & took Bearings. White oak 6 S 31 W 99 links Black Oak 10 N 68 W 69 links. Thence ^{run} West on 9° 30' East at 5 chains set temporary post. Thence ^{run} South at 9° 27' to line between the NE & SE 1/4 of said section. Thence East 5.08 chains to Place of beginning. Thence corrected West 5 chains and set post. White oak 5 N 68 W 52 links Black Oak 10 N 73 E 93 links. Thence ^{corrected} North 10 chains and set post. Black Oak 10 S 45 1/4 W 48 links. Black Oak 10 N 69 1/4 W 38 links. Thence corrected East 5 chains to corner first established in making said Survey.

John G Clark County Surveyor
By Solomon Goodrich Deputy

Recorded March 17th 1854

Attest John G Clark
County Surveyor