

Survey made for Patrick Doyle June 10th 1854
 also for Thomas McArthur in Section 9 Township 3 North
 Range 2 West of 4th P.M. Richard Pofford & William
 Pofford chainmen - first duty sworn.

Commencing at 1/4 section corner on East side
 of said Section whence bears Sugar 14 S 29 2/3 45 links & Sugar
 14 S 79 1/2 79 links (the old bearing & Sugar 14 S 75 2/3 38 links & Oak 25
 S 67 1/2 53 links being destroyed) Thence run West Variation 8° 26' East
 at 12.47 chains intersect Range line Section line 90 links north
 of 1/4 section corner between sections 8 & 9. Thence back East on
 Random line 3 2/3 34 chains & set temporary center post. Thence
 run South Variation 9° East at 40.48 chains intersect Section line
 1 1/2 links West of Quarter Section corner. Then from the same
 temporary center post Variation 9° East run North at 40.23
 chains fall 30 links East of quarter Section corner between
 sections 4 & 9. Thence corrected South Variation 9° 26' East
 20.17 1/4 chains & set post for 1/16 section corner whence bears
 Black Oak 9 N 74 1/2 W 80 links & White Oak 20 N 11 1/2 E 6 3/4 links. Thence
 corrected South 20.17 1/4 chains & set post for Quarter section
 corner whence bears Black Oak 12 N 12 1/2 W 190 1/4 links. Run Oak
 18 S 9 1/4 E 107 links & a Double Line 40 West 4 1/4 links not marked
 but faced on West side. Thence corrected West Variation 9° 31'
 East 19.86 3/4 chains & set post for 1/8 section corner. Whence bears
 Burr Oak 16 N 83 W 57 links & White Oak 14 S 59 E 49 links. Then
 from center post corrected East Variation 8° 35' East 19.86 3/4
 chains & set post for 1/8 section corner. Bearings Sugar 12 N 71 East
 134 1/2 ~~chains~~ links White Oak 16 S 17 E 25 links. Then from center post
 corrected South Var 8° 46' East 20.17 1/4 chains & set post for
 1/16 section corner. Bearings White Oak 15 S 71 1/2 W 17 links. White
 Oak 16 S 64 1/2 E 34 links & Then commencing at quarter
 section corner on East side of said Section run
 Variation 8° 50' East ^{run South} at 40.25 chains fall 23 links West of corner
 sections 9 & 10. 15.216 whence bears White Oak 20 S 78 W 14 links
 Line 14 N 43 W 21 links. Thence West Variation 8° 15' East

This and the following appear to conflict with String line

Center 9-2

PL 157

at 39.89 chains fall 21 links North of Quarter section corner
 Thence corrected East Variation 8° 35' East 19.94 1/2 chains &
 set ^{post for} 1/8 section corner. Bearings White Oak 20 N 27 1/2 E 54 links &
 Sugar 14 N 58 1/2 W 63 1/2 links. Thence run North Variation 8° 45' East
 at 40.33 chains fall 9 links West 1/8 section corner. Then from
 corrected 1/16 section corner on East side of said S. E. 1/4 section
 run West Variation 8° 30' East at 19.94 chains fall 18 links North
 of center post on Range line. Then from said post West
 same Variation at 20.02 chains fall 2 links North of 1/16 section
 corner. Thence corrected East Variation 8° 33' East 19.98 chains
 & set post for 1/16 section corner at equal distances from
 the North and South boundaries of said Quarter section.
 Bearings White Oak 16 S 35 1/2 E 19 links. White Oak 12 S 64 W
 15 links. Also a White Oak 15 N 68 W 45 links marked by some
 previous surveyor.

I hereby certify that the above and foregoing
 is a true and correct copy of the original notes of said
 survey.

Recorded June 12th 1854.

John G. Clark
 County Surveyor