

Field Notes of Survey made for Patrick Doyle in Section 9 Town 3 North Range 2 West by A. H. Banks Deputy County Surveyor June 2<sup>nd</sup> 1854. Thomas Blechly and James Savage Chainmen first duly sworn.

Commencing at 1/4 section corner between sections 9 & 10 thence ran North Par 8° 30' East at 81.53 chains fell 102 links East of 1/4 section corner between sections 9 & 10. Thence corrected South Par 9° 14' East at 40.68 1/2 chains and set temporary center post. Thence West Par 8° 30' East at 40.31 chains fell 21 links south of 1/4 section corner between sections 8 & 9. Then from aforesaid temporary center post ran East Par 8° 30' East at 40.15 chains fell 19 links north of 1/4 section corner between sections 9 & 10. Thence corrected West Par 8° 14' East at 20.23 1/2 chains and set post for 1/4 section corner. Bearing White oak 17 533 1/2 58 links. Sugar 9 178 1/2 & 149. Then continued West on corrected line 20.23 1/2 chains and set post for Quarter Section Corner Bearing. Line 22 845 1/2 & 42 links. Book 12 NW 154 links. Then corrected North Par 9° 8' East at 20.34 1/4 chains & set post for 1/16 section corner. Red oak 9 882 1/2 51 1/2 links. White oak 15 158 & 58 links. Then from center post corrected South 20.34 1/4 chains Par 9° 20' East and set post for 1/16 section corner. Bearing White oak 20 853 1/2 78 links. White oak 20 811 1/2 & 43 links. Then from center post corrected West Par 8° 48' East 20.23 1/2 chains and set post for 1/8 section corner. Bearing Bun oak 15 818 & 42 links. White oak 16 178 1/2 115 1/2 links. Then commencing at 1/4 section corner between sections 9 & 10 retraced the South boundary of the SW 1/4 of section 9 & found the length thereof to be 39.59 chains & the variation 9° 34' East. Then retraced the West boundary of said quarter section & found the length thereof to be 41.15 chains & the variation to be 10° 9' East. Then crossed said quarter section from East to West & from North to South & set post for 1/16 section corner

Center 9  
2

in center of said SW 1/4 section at equal distances from the East & West boundaries thereof & from the North & South boundaries thereof

The variation of the East 1/2 of the East-West line being 10° 8' East & the length thereof 19.58 chains. The variation of the North half of the North-South line being 12° 39' East & the length thereof 20.55 chains bearing in center of SW 1/4 of said section 9. Line 12 N 24 1/2 W 102 links NW 1/4 118 W 52 links

A true record of notes of said survey recorded June 13<sup>th</sup> 1854 John G. Clark County Surveyor

Survey made for William Clement of the NW 1/4 of the N.E. 1/4 of section 23. T4 North Range 6 West 4<sup>th</sup> R.M. May 9<sup>th</sup> 1854 by Solomon Goodrich Deputy County Surveyor. William Lewis & Washington Scott Chainmen first duly sworn.

Commencing at 1/4 section corner between sections 14 & 23. Thence East variation 8° 24' East 19.99 chains to 1/8 section corner found in previous survey for A. A. Bennett. Thence South variation 9° 54' East 20.04 1/4 chains to State 1/16 section corner set in said previous survey. Thence West variation 8° 17' East 20.01 1/2 chains to State set in said previous survey for 1/16 section corner. Thence North variation 9° 35' East 40.11 1/4 chains to place of beginning

A true record of the notes of said survey. Attest John G. Clark County Surveyor. Recorded June 15<sup>th</sup> 1854.