

Survey made in Section 15 Township 3 North Range 2 West July 11<sup>th</sup> 1854 by John G. Clark County Surveyor for James Rankin, Robert Ellis, John Leatrice, Edmund Chase, Greenbury Stille, James Edman, James & Thomas J. Horn.

The N<sup>W</sup> 1/4 of the S<sup>W</sup> 1/4 William Pofford and Richard Pofford Chainmen first duly sworn.

Commencing at corner of Sections 9, 10, 15 and 16 bearing S 87° 45' East. Thence East at 40.21 chains fell 15 links South of quarter section corner thence corrected West 20.11 chains & set post for 15 section corner Bearings White Oak 12 N 53° E 100 links. White Oak 15 S 12° E 140 links. Then from the aforesaid Quarter section corner ran South bearing 8° 45' East at 80.45 chains fell 110 links West.

Then from Quarter section corner on East side of said section ran West at a bearing of 9° East at 13 chains fell 15 links South of center post on true north South line through center of section. Then from said center post continued West at 40.33 chains fell 57 links North of 14 section corner on line between sections 15 & 16. Old bearing Sugar 12 N 32° E 13 links. new bearing in line of old bearing destroyed N Oak 14 S 26° W 84 1/2 links. Thence South ran 9° 20' East at 40.20 chains intersect at corner of Sections 15 & 21 & 22. Thence East bearing 9° East at 40.45 chains fell 35 links North of Quarter section corner. Thence corrected West 20.22 chains. Thence North ran 9° 20' East at 40.04 chains fell 41 1/2 links East of 15 section corner corner from which bears Elm 14 N 48° 53' E 63 1/2 links. Elm 10 S 45° W 95 links. Then corrected & set post for 16 section corner South center Red Oak 15 S 28° E 16 links. Sugar 12 S 25° W 19 links. Thence ran West ran 9° East at 20.09 chains intersect on line through center of the S<sup>W</sup> 1/4 of said section 10 links South of set post set on said random line. Then from said point of intersection continued West at 40.09

W.M.P.

11 chains fell 19 links South 16 section corner corner. Bearings to same Red Oak 15 S 8° E 64 links. Elm 14 N 51° E 19 1/2 links. Thence corrected East 20.05 chains & set post for 16 section corner Bearings Red Oak 16 N 62° W 18 links. Sugar 9 East 17 links. at equal distances from the north & south boundaries of said S. W. 1/4 section.

Then corrected & set post for Quarter section corner at center of section at equal distances from the north & south & at equal distances from the East & West boundaries thereof. White Oak 15 N 51° W 166 links. Red Oak 12 N 57° E 179 links.

Then from 15 section corner West of center ran North bearing 9° 20' East at 40.39 chains fell 8 links East of 15 section corner. Then from corner of sections 9, 10, 15 & 16 ran 9° 20' East ran South at 40.15 chains fell 1 link East of Quarter section corner thence corrected North 20.07 chains and set post for 16 section corner Bearings White Oak 28 N 34° W 81 links. White Oak 24 N 12° E 255 links.

Thence East bearing 9° East at 20.03 chains fell 15 links South of temporary post set at center on random line. Then from said center post continued East at 20.12 chains fell 3 links South of 16 section corner. Corrected & set post for same White Oak 15 N 32° W 198 links. Hoickoy 10 N 9° W 97 links. Thence corrected West 20.07 chains & set post for 16 section corner. Bearing White Oak 25 S 28° E 5 links. White Oak 24 N 66° W 255 links.

The N<sup>W</sup> 1/4 of the S<sup>W</sup> 1/4 for James Rankin.  
The S<sup>E</sup> 1/4 of the S<sup>W</sup> 1/4 for Greenbury Stille. The S. E. 1/4 of the N<sup>W</sup> 1/4 for Edmund Chase. The N<sup>W</sup> 1/4 of the S<sup>W</sup> 1/4 for Robert Ellis. The S. E. 1/4 of the S<sup>W</sup> 1/4 for John Leatrice.

A true Record of the Notes of said Survey.  
Attest

Recorded August 4<sup>th</sup> 1854. John G. Clark. County Surveyor.