

107 Thence corrected South Variation  $10^{\circ}22'$  East at 73.10 chains intersect at quarter section corner.

Then commencing at quarter section corner in West of said section corrected thence West  $9^{\circ}6'$  East at 42.11 chains intersect at quarter section corner for said section in Range line.

A true Record of said Survey.

Attest

Recorded <sup>Septem</sup> August 1st 1854. John G. Clark  
County Surveyor

No 99

Survey made for Mark M. Seast by Solomon Goodrich Deputy County Surveyor of a lot containing one acre ~~and two~~ ~~lots~~ ~~in~~ the S.E. corner of the N.W. 1/4 of section 12, T.4, R.6, April 15th 1854. Henry Dulick & Joseph Mory chainmen first duly sworn.

Commencing at 1/4 section corner on Range line on East side of said section 12 ran thence West  $9^{\circ}30'$  East at 79.30 chains intersect section line 40 links South of 1/4 section corner. Thence corrected East 39.65 chains  $9^{\circ}15'$  East. Thence South from 1/4 corner between sections 1 & 12  $9^{\circ}30'$  East at 39.97 chains and fell 56 links West of <sup>temporary</sup> 1/4 section corner. Then from said temporary center past continued South Variation  $10^{\circ}$  East at 79.97 chains intersect section line at 1/4 section corner. Thence corrected North  $10^{\circ}$  East 39.987 chains & set past in mound for 1/4 section corner. Thence corrected North  $10^{\circ}18'$  East 39.987, intersect at 1/4 section corner on line between sections 12 & 13.

Then corrected West from 1/4 section corner in center of section Variation  $9^{\circ}12'$  East.

Thence North from 1/4 past at center of section

Variation  $10^{\circ}18'$  East 20 feet. Thence West 30 feet  $9^{\circ}12'$  East to a post in mound the South East corner of the said lot. Thence North  $10^{\circ}18'$  East 190 feet to a post in mound. Thence West  $9^{\circ}12'$  East 231 feet to a post in mound. Thence South Variation  $10^{\circ}18'$  East 190 feet. Thence East  $9^{\circ}12'$  East 231 feet to the place of beginning containing one acre & two rods 330 feet.

A true Record of Notes of said Survey.

Attest

Recorded Septem 1st 1854. John G. Clark  
County Surveyor

No 100

Survey made of the N.E. 1/4 of section 13 Township 4 North Range 6 West April 17th 1854 for L. Basford by Solomon Goodrich Deputy County Surveyor. William Jordan & Mark M. Seatt chainmen first duly sworn.

Commencing at 1/4 past between sections 12 & 13 Variation  $10^{\circ}$  East thence run South at 80.40 chains intersect section line 47 links East of 1/4 section corner. Thence correct North 40.20 chains and set temporary quarter section past. Then from 1/4 past between sections 13 & 14 ran East  $10^{\circ}$  East at 39.42 chains fell 22 links North of temporary quarter section past. Then from said past continued East at 78.95 chains fell 9 links North of 1/4 section corner. Thence corrected West 39.477 chains  $9^{\circ}52'$  East & set past for 1/4 section corner in mound. Thence West 39.477  $9^{\circ}41'$  East to 1/4 corner on line between sections 13 & 14. Then from said center past corrected North Variation  $9^{\circ}45'$  East 40.20 chains to 1/4 corner between sections 12 & 13.

A true Record of Notes of said Survey.

Attest

Recorded August 22nd 1854. John G. Clark  
County Surveyor