



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Original				
4	White Oak	7	N 42 E	41	Corner identified by remains of original bearing tree
	" "	7	S 85 W	32	
5	Corner located				9 1/2 links east of true corner S 75 R 1
7	Br Oak	13	S 36 W	59 1/2	Established by entire re-survey of section line. No trace of original bearing.
	Br Oak	14	S 61 W	77 1/2	
8	Cottonwood	28	S 18 1/2 E	199	Established 148 South of 1/4 post for Sec. 1 T 4 R 2 which corner was found by one old bearing tree
9	Br Oak	10	S 67 1/2 W	95	
	White Oak	10	N 33 W	154	
12	Br Oak	28	S 53 W	352	
20	Br Oak	3	N 77 1/4 W	33	
	" "	12	S 62 1/2 W	14	
21	Br Oak	12	S 84 E	14	
	" "	10	N 43 1/2 W	49	
22	Br Oak	5	S 75 E	3	
	Br Oak	3	N 21 W	25	
25	Br Oak	7	- 25 W	-	
	Black Cherry	12	N 21 E	3.39	
26	White Oak	24	N 68 W	68	
	Black Cherry	6	S 77 1/2 E	19	
27	Br Oak	6	N 49 1/2 E	29	This corner was found as previously set and re-established by me
	" "	4	S 72 1/2 E	29 1/2	

Surveyed Nov. 27th 1876

STATE OF WISCONSIN, } ss.  
GRANT COUNTY,

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4-inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian ..... East. The variation of needle adopted in establishing corners is 8° 20' East.

WITNESS my hand this 2nd day of March A. D. 1877.

..... } CHAINMEN.

Joel Barber SURVEYOR.