



E Hehn

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Burr Oak Br Oak	18 13	N 38 W N 82 1/2 W	135 122	New bearing tree Original - Cut down but a sprout 1 inch thick is growing from the south side of stump
4	Br. Oak	8	N 22 W	18	Now - corner identified by remains of old bearings
5					One bearing tree standing (No)
6					Bearings gone - An old stake under fence showed true by Squire Richie
7	White Oak White Oak	8 12	S 59 1/2 E S 28 1/2 W	108 107	Established by resurvey of whole section line No trace of original bearings found
8					Fence corner considered correct
9					Set stake without bearings
12					Set stake without bearings
17					Set stake without bearings
20	White Oak "	4 8	S 16 1/2 W N 29 W	20 28 1/2	
23	White Oak "	20 20	S 86 1/2 W S 22 E	134 122	
Surveyed for Mr. Hehn Feb. 23 ^d 1877					

STATE OF WISCONSIN, }
GRANT COUNTY, } ss.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian _____ East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 16th day of April A. D. 1877.

George Speed
Frank Schipper } CHAINMEN.

Joel Barber SURVEYOR.