



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
4	Set stake		without bearings		Established this corner by measuring from the 1/4 post East of it to the one west of it and dividing proportionally, but set it north by measure from a supposed bearing
5	Original				Bearings satisfactory
6	Original				Bearings satisfactory
7	Original				Bearings Exact
8	Original				Both bearings in good order
9	White Oak	12	N 70 1/2 W	47	Trees blazed but not scribed
	White Oak	11	S 6 W	17	
12	White Oak	26	S 75 3/4 W	23	" " " " "
	White Oak	30	S 1 W	76	
21	Set stake		but no trees were near enough for bearings		Surveyed for Slight State Sept. 1877

CERTIFICATE OF SURVEY.

STATE OF WISCONSIN, } ss.
 GRANT COUNTY, }

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 20' East.

WITNESS my hand this 12th day of September A. D. 1877.

James Currant } CHAINMEN. Joel Barber SURVEYOR.