



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
7	Original	Govt	Corner		One bearing in good order
9	White Oak Red Oak	5 6	S 15 1/2 E N 78 1/2 W	9 1/2 17	I set this corner in 1873 after a very careful division of the section
12	Br Oak Br Oak	15 20	N 49 W S 56 1/4 W	25 11	Set as above remark
17	Black Oak White Oak	10 7	N 18 W N 47 E	3 1/2 8	" " "
21	Set stake	without bearings			A spring is 392 links south and 279 links west through which runs the line from 26 to 28
22	found	Ancient stone	corner		
23	Br Oak Br Oak	24 26	N 78 1/2 E S 22 E	164 46 1/2	
25	Black Walnut Black Walnut	6 6	N 30 E S 41 W	25 21	
26	White Oak White Oak	27 315	N 85 W S 59 W	20 12	A double White Oak E Corner 392 links south of No. 25
28	Set Stake	279 links due east of spring and 392 links south of No. 21			
27	Set Stake	392 links south of No. 22			

Surveyed for Lewis Glass  
Feb 28th 1878

STATE OF WISCONSIN, } ss.  
GRANT COUNTY,

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County

and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian ..... East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 13th day of March, A. D. 1878.

Charles Glass