



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Br Oak W Oak	7 26	N 53 E N 78 1/2 W	85 393	Same as No. 2 page 28
4	W Oak	12	N 51 E	38	This was the only bearing found and the mark faced S.W. which with the length and course of adjacent lines induces me to conclude that it wrongly noted S.E. when it was N.E.
6	Black Oak White Oak	14 12	N 88 1/2 E S 84 W	74 33 1/2	Original bearings extant but dead
7	Hickory W Oak	7 10	S 3 E S 84 1/2 W	476 204	Same as No. 5 of page 28
8	Br Oak Black Oak	8 12	N 78 1/2 E N 14 3/4 E	26 22 1/2	Original and unmistakable A new bearing tree
9	W Oak W Oak	29 27	S 58 W N 77 1/2 W	20 1/2 17 1/2	Set at intersection of true corrected quarter lines through the entire section
12	White Oak " "	12 11	N 30 1/2 W S 21 W	40 19	Set Rock 18x6x3
17	Br Oak Br Oak	8 9	S 89 W N 10 1/4 W	14 1/2 39	
20	Hickory " "	4 5	N 17 1/2 W N 20 E	67 1/2 72 1/2	
23	White Oak Black Oak	7 7	S 43 1/2 W S 68 3/4 E	29 41	

Surveyed for Jerome Hill
March 7th 1878

STATE OF WISCONSIN, } ss.
GRANT COUNTY, }

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 18th day of March A. D. 1878.

..... } CHAINMEN.
..... } Joel Barber SURVEYOR