



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Sugar	10	S 73 1/4 E	38	Original bearing tree still good Ash - a new tree blazed by myself - the other original bearing being gone
	Ash	10	N 42 E	41	
9	White Oak	30	S 10 1/2 W	83	
	"	29	N 49 1/4 E	103	
11	White Oak	31	S 2 1/4 E	79	
	Black Oak	20	S 35 1/2 E	132	
20	White Oak	26	S 47 1/2 W	37	
	Hickory	3	S 78 1/2 W	19	
21	White Oak	29	S 42 E	10	
	"	26	N 2 1/4 E	54	
22	Set stake without bearings				
17	Set stake in field of Caspar Reedy without bearings				
19	Ancient corner set by Wm N Reed surveyor				

CERTIFICATE OF SURVEY.

STATE OF WISCONSIN, }
 GRANT COUNTY, } ss.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 27th day of March A. D. 1878.

Caspar Reedy
Florian Shoyer } CHAINMEN.

Joel Barber SURVEYOR.