



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	White Oak	24	N 86 E	11	Original - in good order - Stump of the other tree remaining Set corner Stone
4	White Oak White Oak	30 5	S 3 1/4 E S 69 1/2 E	51 26	New } Old stone corner standing but none of the original bearing trees.
6					Both bearing trees in good order
7	White Oak	25	S 65 W	48	Original - Set corner stone 24 x 24 x 10
9					Adopted the corner established previously by Wm. N. Reed
19	White Oak	24	S 9 E	85 1/2	
20	White Oak White Oak	24 8	S 31 1/2 E N 3 E	64 1/2 83	Set corner Stone 20 x 8 x 5
21					Set corner Stone
22	Black Ash Lynn	15 13	S 79 1/2 W S 76 E	78 100	Set a good corner stone
23	White Oak White Oak	7 26	N 38 E S 17 1/2 W	27 63	Set corner Stone 20 x 13 x 2 1/2
<p>Surveyed for J. Plush and J. Monerch November 7th + 8th 1878</p>					

STATE OF WISCONSIN, }
GRANT COUNTY, } ss.

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this first day of December A. D. 1878.

Henry Rich
Wisconsin } CHAINMEN.

Joel Barber SURVEYOR.