



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
2	White Oak White Oak	7 13	S 86 W S 52 1/2 E	40 60	Original bearing, yet in good order A new bearing
3	Hickory White Oak	2 3	S 51 W S 23 E	10 11	New bearings to the corner established by me in 1876
5					Ancient stone heap, the reputed corner but no other evidence
6	White Oak White Oak	40 7	N 12 W N 44 3/4 E	104 40	Established by reurvey of the whole section line Old bearings not perceptible.
7	White Oak	28	S 34 E	22	Old In good order The other tree nearly disappeared
8	Old Stone corner				Bearings still perceptible
9	Burr Oak White Oak	18 18	S 34 E N 49 E	22 49	
15					Stake set temporarily - to correct - move east - 16 1/2 links and North 2 1/2 links
16	Black Oak No other tree taken	7	N E	2	
17	S.E. cor. of Kitchen Alm 13	13	N 57 1/4 W N 27 1/2 W	80 162	Set Stone 18 X 3 X 4
19	Hickory Sugar	14 14	N 76 1/2 E S 16 W	30 26	These trees had been used as bearings in some previous survey
20					Set a stake beside a sugar tree stump 14 inches
21	Sugar White Oak	26 20	S 57 W S 61 1/2 E	16 1/2 50	
22	White Oak White Oak	8 13	N 57 E S 48 1/2 W	67 76	Set at intersection of true 1/4 # lines

CERTIFICATE OF SURVEY.

Survey finished Dec. 11th, 1878

STATE OF WISCONSIN, } ss.
GRANT COUNTY,

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 20' East.

WITNESS my hand this 26th day of December A. D. 1878.

Benjamin Jeffers
Charles Wahmshley Jr. } CHAINMEN.

Joel Barber SURVEYOR.