



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Set Stone		16 X 14 X	4	The sugar Maple bearing tree standing but dead
5+6	Established by original bearings				
7	Found by survey of whole section line - Original bearings entirely gone				
8	Hickory Br Oak	7 5	N 1 1/2 E S 41 W	19 1/2 23	Found by resurvey of whole sec line Original bearings not perceptible.
9	Red Oak Hickory	5 3	S 76 3/4 W N 42 E	43 1/2 2	
11	White Oak White Oak	13 8	S 55 1/4 E N 80 1/2 W	55 41	
12	White Oak White Oak	24 2	S 81 1/2 W N 14 E	53 6	
13	White Oak White Oak	7 7	West S 43 E	7 10	
15	Stake set beside a sugar stump 14				
17	Set stake without bearings				
18	Set temporary stake equidistant from 15 to 17 on corrected line.				
20	Black Walnut Elm	4 3	N 74 W N 47 1/4 W	49 1/2 49	Set by resurvey of whole section line between sections 16 + 21
21	Built a Stoneheap on the corner. No bearings				
23	Black Walnut 6 N 78 W 55 Near house of A.B. Chapman				
6	Red Oak Red Oak	24 20	S 28 W S 17 E	68 53	This corner is equidistant from 9 to 17

STATE OF WISCONSIN, }  
GRANT COUNTY, } ss.

CERTIFICATE OF SURVEY. Survey finished Dec 16th 1878

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian is 8° 20' East. The variation of needle adopted in establishing corners is 8° 20' East.

WITNESS my hand this 26th day of December A. D. 1878.

Charles Wambsler  
Holloway Sticklins } CHAINMEN.

Joel Barber SURVEYOR.