



Surveyed for H. E. Rice +
Edward Dugan
May 23d.

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
1	Black oak 1 Corner stone	6 16	S 45° W X 9 X 5	3 1/2	Corner identified by stump of one bearing tree viz. 40 18 S 1 W 595
2	Cherry Set corner stone	5 16 X 12 X 10	N 12° W	15	See No. 3 page 37
3	Set corner stone				near S E corner of a small cemetery. Had good evidence of a former corner.
4	Found an accepted corner				Stake but no bearing trees
5	See No 7				Page 37
6	Set Locust stake				in top of bank ^{equidistant} from 2 to 3 and in reputed old line.
7	Replanted corner stone				16 X 8 X 7 in old mound.
8	Burr Oak Corner stone	8 18 X 13 X 5	S 82° E	45	Established after resurvey of whole section line One reputed bearing tree stump shown but not satisfactory.
9	Set corner stone				at the point fully identified as the corner made by Overton, Co, Surv May 21st 1857
11	Burr Oak	8	S 2° E	148	Set rock at corner
12	Rock				18 X 12 X 10
13	Ancient corner stone				correct
14	Rock				17 X 13 X 10
15	Rock				10 X 6 X 6
16	Ancient corner stone				
17	Black Oak	12	N 9 1/2° W	373	Also set stone at corner
18	Black Oak Black Oak	14 14	N 82 1/2° W S 26 1/2° E	2 1/2 60	Set corner stone 14 X 12 X 9

STATE OF WISCONSIN,
GRANT COUNTY, } ss.

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this first day of June A. D. 18 79.

Benjamin Weeks
Nicholas Murray } CHAINMEN.

Joel Barber SURVEYOR.