



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
1	Ancient corner Stone				
2	Corner Stone 18 x 7 x 6 inches				Corner located by evidence of fences ditches and neighbors
4	Ancient Corner Stone				
5	Large cedar Stake				
6	Box Elder Set corner rock	18	N 13 E	15	
7	Ancient corner Stone and cedar stake				Established by re-survey of whole section line
8	Set corner Stone 22 x 10 x 9 - Wild Crab	7	N 42 E 35 1/2		corner 48 links south of former position of stone
9	Set rock 14 x 8 x 8				Set this corner 3 links north and 2 1/2 links south of previously set stones, which I dug up. Very queer.
11	Set rock	20 x 10 x 8			
15	Cottonwood	24	S 7 3/4 W	287	Set oak stake
13	Set Rock	16 x 12 x 8			
16	Cottonwood Cottonwood	20 28	S 63 1/4 E N 52 E	216 120	Set stake
17	Ash Butternut	15 7	N 31 1/4 E S 53 1/4 E	24 13 1/2	Set rock 14 x 10 x 8
18	Cottonwood	22	S 9 1/2 E	48 1/2	Set rock 10 x 8 x 6
19	Red Oak	4	N 33 W	26 1/2	Set rock 16 x 12 x 10 above some stone coal.
20	Set rock	12 x 8 x 6			
21	Set rock	18 x 6 x 4			
22	Set a corner Stone,				

STATE OF WISCONSIN,
GRANT COUNTY, } ss.

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian in establishing corners is 8° 30' East. The variation of needle adopted East.

WITNESS my hand this 2nd day of June A. D. 1879.

William Hooseman
Bernard Budden } CHAINMEN.

Joel Barber SURVEYOR.