

4-1-1

8° 44' 39.86 1868
10° 20' 39.76

412



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
1	Ancient corner stone				
2	Ancient corner stone				
5	S.E. corner of foundation of Dooney's House		N 50 1/4 W	111	Corner Established after survey of whole line North side of sec, 4
6	Ancient stone corner				
7	Ancient stone corner				
8	Ancient corner				See No 6 page 41
9	Willow set rock	13	S 27 1/2 W	375 1/2	This corner is 8 links exactly west from a corner stone previously set.
11	Willow Elm	18	N 57 3/4 W	5.78	Set a good corner stone
		8	S 77 1/4 E	3,40 1/2	
13	Set rock by N+S. measurement of section line but not alligned.				under fence
14	Set rock on true E+W. line but not alligned N+S.				under fence
15	Set a corner stone				
17	Set a corner stone				
18	Set a true corner stone				at intersection of 1/4 1/4 lines

Established all quarter quarter corners at proportional distances between known section and quarter section corners according to the original field notes of the Govt. Survey.

STATE OF WISCONSIN, } ss.
GRANT COUNTY,

CERTIFICATE OF SURVEY.

Surveyed June 4th 5th 1879

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian. East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 10th day of June A. D. 1879.

Henry Mitchell
James Glasson } CHAINMEN.

Joel Barber SURVEYOR.