



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	White Oak Hickory	8 7	N 89 3/4 W N 89 3/4 W	18 37	Found an old stake which is the reputed corner No bearings found
4	White Oak Br. Oak	8 6	S 30 E S 79 E	84 72	Ancient rock and Stake - bearings gone
6	Br. Oak	6	S 23 W	23	Found one bearing long since prostrate - SW No trace of the Br. Oak
7	Br. Oak White Oak	7 8	N 56 E N 16 W	51 94	No trace of bearings left. Set corner by survey of the whole section line. Line runs 78 links south of the old erroneous corner claimed by J. Heffron
20	Ironwood Basswood	10 8	N 44 W N 55 1/2 W	14 30	But marked in wrong direction by former survey
23	No bearings taken				Set stake 36 links south of Heffrons fence
					Surveyed for Thomas Solon Dec. 12th 1879

STATE OF WISCONSIN, } ss.
GRANT COUNTY, }

CERTIFICATE OF SURVEY.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 15th day of December A. D. 1879.

Henry Manning
James Mc Gill } CHAINMEN.

Joel Barber SURVEYOR.