



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
4	White Oak Black Oak	13 16	East S 37 W	34 48	New bearings to old corner stake set or accepted by J. W. Blanding in former survey
7	Elm Red Elm	20 16	S 5 E S 17 E	258 1/2 289	Old bearings gone - corner established by return of entire section line
8	Hickory Br Oak	8 10	S 17 1/2 E S 76 E	181 40	New bearing Original - the other old bearing stumps visible
9	White Oak Hickory White Oak	13 7 29	N 34 W S 76 1/2 E W N 5 1/2 E W	26 49 59	
12	White Oak "	20 14	S 56 E N 81 1/2 E	63 64	
13	B. Cherry Br Oak	6 4	N 71 1/2 W N 54 1/2 W	41 20	
14	White Oak "	24 16	N 19 W N 68 1/2 E	26 76	
11	White Oak "	15 18	S 64 1/2 W N 32 W	17 39	Surveyed for Anton Dvorak & Albert Dvorak 19th to 25 Feb 1880
23	Br Oak "	8 7	N 86 1/2 E S 26 E	158 128 1/2	
24	Pin Oak Black Oak	8 14	S 46 3/4 W N 19 3/4 E	80 164 1/2	
6	White Oak	6	N 76 W	11	New - Stumps of both original bearings sound
25	Br Oak	2	N 60 E	17	
1					Corner for T 8 R 1 well established
5	Stone heap set by Wm. N. Reed for land in Town 7 according to witnesses				

STATE OF WISCONSIN, }  
GRANT COUNTY, } ss.

I, Joel Barber, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian ..... East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this Eighth day of March A. D. 1880.

Albert Dreicht  
Joseph Shaker } CHAINMEN.

Joel Barber SURVEYOR.