



Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
5	White Oak "	5 3	S 26 E N 18 1/4 E	10 1/2 15 1/2	Corner identified by the west bearing-stump showing mark and ingrowing wood
6	White Oak Black Oak	10 6	S 55 1/4 E N 80 W	38 1/2 6 1/2	Stump of original bearing extant
7					N. E. bearing in good order N W " cut - stump remains
8					S E bearing in good order S W " cut - stump remains
9	White Oak "	26 28	S 19 E S 70 E	420 363	
Section quartered and No. 9 established on the 19th day of January 1880 for G. Thomson and Patrick Shea					
The line from 5 to 9 established for W. Nestadok Sept. 22nd 1880					

CERTIFICATE OF SURVEY.

STATE OF WISCONSIN, } ss.
GRANT COUNTY,

I, Joel Barber, County Surveyor in and for the County

and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 8° 30' East.

WITNESS my hand this 24th day of September A. D. 1880.

Joel Barber
Assistant } CHAINMEN.

Joel Barber SURVEYOR.