



For Wm White - A + J Abrams, A + J. P. Williams, + A. Ellis.

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
1	White Oak	9	N 78 1/2 W	23 1/2	Original
	" "	12	S 32 E	24	
3	Stake set in highway				This corner was located by running from 6 South 1 mile to 14 cor + running from 7 East 1 mi to 14 cor + intersection of line corner was located.
4	White Oak	20	S 76 E	380	Original
	Burr Oak	7	S 69 W	154	
5	Black Oak	6	N 6 1/2 E	43	This corner was located from the stumps of the original bearing trees some of which were in good condition
	W Oak (Stump of)	18	S 6 1/2 W	99	
6	Stone set in highway				
7	White Oak	30	N 2 E	51 1/2	Original
	Stump of W. Oak	24	S 34 E	54	"
9	10 x 5' Stone at intersection of 1/4 lines				
10	White Oak	20	S 88 1/2 E	34 1/2	
11	Black Oak	10	N 65 W	75 1/2	
14	White Oak	5	S 2 1/4 W	50	
15	White Oak	9	S 74 E	29	
	Black Oak	4	S 72 1/2 W	23	
17	Set Stone				
20	Set Stake		midway between	7 + 3	
21	Set Stake				
23	White Oak	14	N 37 1/2 E	64 1/3	
	" "	13	N 42 3/4 W	126	
	Stone 18 x 8 x 3"				
25	Black Oak	12	N 30 E	13	
	White W. Oak	8	S 10 1/2 E	24 1/4	

CERTIFICATE OF SURVEY.

STATE OF WISCONSIN, } ss.
GRANT COUNTY,

I, J. C. Scott

County Surveyor in and for the County

and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 7° 20' East.

WITNESS my hand this 1st day of September A. D. 1881

CHAINMEN.

J. C. Scott

SURVEYOR.