



Survey made for Mrs. C. E. Field Nov. 20th 1881.

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
2					Located corner from stump of one original bearing tree and remains of others.
5	Black Oak Burr Oak	14 7	S 24 East S 65 1/2 W	172 1/2 109	New bearings located by the stump of one bearing tree and by finding where other original bearing tree stood by digging
6	Stone set when I made survey for A. H. Sample.				found remains of both original bearing trees & stone from them.
9	Stone set by Foreman in 1841				
11	Stone set midway from 9 to 5				
15	Stake put in a hole made with brood saw, located midway between 5 and 2.				
18	Stake put into a hole made with brood saw, at intersection of 18 1/2 lines above stone set.				
19	Stone set in a stump of a large white oak tree about which the tree was 24 or 26 inches diameter when laid put under stump & saw.				
20	Stake over line in a hole				
21	Stake				
22	Stake + line				

STATE OF WISCONSIN,
GRANT COUNTY,

CERTIFICATE OF SURVEY.

I, J. C. Scott

County Surveyor in and for the County

and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 40 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 7° 30' East.

WITNESS my hand this 24 day of Dec A. D. 1881

R. H. Hendrick
J. Gibson

CHAINMEN.

J. C. Scott

SURVEYOR.