



For J. Gibson Dec 7th 1881.

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
1					One original bearing tree in good condition
5	Blk Oak Burr Oak	14 7	S. 24 E S 65 1/2 W	172 109	See notes for No. 5 on page 107. This is same corner
8	Stone set in road				One original bearing tree standing in good condition. Clamp of other tree remaining
9	Stone set by firmman				in 1841
10	Stone set on a hole that was made with an iron bar and filled with lime Blk Oak White Oak	13 4	S 42 1/2 W S 42 05 E	70 80	
30	White Oak Imbr White Oak	14 6 x 10	S 68 1/2 E S 27 3/4 E	179 158	
31	Stake in field				From 30 to 31. N 39 1/2 W 7.13 ch " 31 to 32. S 53 1/2 W 57 "
32	Stake in field				" 32 " 33. N 15 1/2 W 17.97 " " 33 " 10. North 18.83 " " 10 " 5. East 20.10 "
33	Stake in field				" 5 " 9. South 40.21 " " 9 " 30. West 10.26 "

STATE OF WISCONSIN, } ss. **J. C. Scott**, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 40 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is 7° 15' East.

WITNESS my hand this 24 day of December A. D. 1881.

John Crawford
Wm. Pallisa } CHAINMEN. *J. C. Scott* SURVEYOR.