



To Daniel Taylor April 13th, 1883.

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
4	Stone set by some previous survey. Black Oak	12	S 39 W	10	New. The stone agrees with the remains of the original bearing trees
7	White Oak Cottonwood (small)	8 12	North 36 1/2 W N 87 1/2 W	60 1/2 53	New Bearing trees Established corner by running out whole line from 4 to 3. Also found where original trees stood by digging
8	White Oak " "	19 9	S 88 E N 61 W	49 11	One stump badly decayed remains. In good condition
9	Burr Oak Black "	6 14	S 13 W S 30 1/2 W S 57 1/4 E	6 1/2 48 55	At intersection of 14 lines

CERTIFICATE OF SURVEY.

STATE OF WISCONSIN, }  
GRANT COUNTY, } ss.

I, J. C. Scott, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian..... East. The variation of needle adopted in establishing corners is 7° 30' East.

WITNESS my hand this 23rd day of April A. D. 18 83.

Daniel Taylor CHAINSMEN.

J. C. Scott SURVEYOR.