



Surveyed for John Murray

Corners	Bearing Trees	In. Dia.	Courses they Bear	Links Distant	REMARKS
3	Original Cornu				One original B.T. in good condition & stump of other
6					Located corner by finding where orig B.T. stood
7	Black Oak Hickory	13 8	N 30 E S 86 E	46 1/2 11 1/2	Created cor from where original B.T. stood and made new bearing
20	Black Oak White Oak	20 22	N 73 1/2 W N 78 1/4 E	14 0 9 5	This corner is south 13 links and west 4 1/2 links from where Saml C. Miller placed it in 1844. I put it midway between 7 & 3 and in same straight line
21	White Oak "	10 6	S 42 E S 65 1/2 E	24 54	Midway between 9 & 7. I run the two 1/4 Sec lines to get 19.
22	White Oak "	5 7	S 45 W S 24 W	31 8 1/2	Located at intersection of 1/8 & 1/16 lines.

STATE OF WISCONSIN, }
 GRANT COUNTY, } ss.
 I, *J. C. Scott*, County Surveyor in and for the County and State aforesaid, do hereby certify that I have executed the Survey represented by the foregoing Plat and annexed Field Notes of Survey, in accordance with the State Laws and Instructions of the Commissioner of the General Land Office. Scale, 80 chains to 4 inches. The figures in red ink are the lengths of the lines as stated in the Field Notes of the Government Survey.

Declination of the Magnetic Meridian from the True Meridian East. The variation of needle adopted in establishing corners is East.

WITNESS my hand this *3rd* day of *September* A. D. 18 *83*

D. P. Cologan
Phos. C. Lewis } CHAINMEN. *J. C. Scott* SURVEYOR.