



**PROPERTY DESCRIPTION**

A parcel of land in the NE¼ of the SE¼ of Section 30, Township 6 North, Range 2 West, Town of Fennimore, Grant County, Wisconsin, more particularly described as follows:

Commencing at the north quarter corner of said section 30, marked by a Parker-Kalon nail in the centerline of U.S. Highway-61; thence South 3° 39' 41" West, 361.49 feet; thence South 1° 47' 24" West, 620.00 feet; thence South 13° 29' 21" East, 860.58 feet; thence South 41° 18' 11" East, 2049.77 feet to a one inch iron pipe, the point of beginning; thence North 31° 02' 50" East, 271.30 feet to a one inch iron pipe; thence South 58° 57' 10" East, 256.01 feet; thence South 31° 02' 50" West, 428.84 feet to a one inch iron pipe in the northeasterly right of way line of U.S. Highway-61; thence along said right of way line North 25° 25' West, 51.38 feet to a one inch iron pipe; thence along the arc of a curve in said right-of-way concave to the southwest of radius 3080.38 feet (recorded as 3334.04 feet) and central angle 4° 38' 14", and whose long chord bears North 27° 44' 07" West and is 249.25 feet long, to the point of beginning, said parcel containing 2.376 acres.

**LEGEND**

- - 1" Iron Pipe Set This Survey.
- - 2" Iron Pipe Found In Place

I, Gregory J. Hofmeister, Registered Land Surveyor, hereby certify that the above map and accompanying survey are correct to the best of my knowledge and belief.

*Gregory J. Hofmeister*  
9/9/74

**NOTE**  
Bearings for this survey based on a record bearing of N 25° 25' W for the center line of U.S. HIGHWAY 61. South of STA. 553 + 26.9.

	REVISIONS 10-8-74	DAVY ENGINEERING CO. LA CROSSE - WISCONSIN
	Survey of <b>CITY OF FENNIMORE</b> <b>SEWAGE TREATMENT SITE</b> Sec. 30, T6N, R2W TOWN OF FENNIMORE GRANT COUNTY, WISCONSIN	PROJECT NUMBER: 1050-1
NOTEBOOK NO. 548	DATE: 9-9-74	DRAWN: RRH
SCALE: 1" = 30'	CHECKED:	SHEET OF: