

SURVEY PLAT

52
 - (GRINDEL - ROH LEASE)
 - DDCFB9410PWS

OF A PARCEL OF LAND LOCATED IN E 1/2 OF SECTION 9, T 3 N, R 1 W OF THE 4TH P.M., GRANT COUNTY, WISCONSIN, AND BEING MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT A STONE MONUMENT MARKING THE E 1/4 CORNER OF SECTION 9, T 3 N, R 1 W OF THE 4TH P.M., GRANT COUNTY, WISCONSIN, THENCE N 89°24'39" W 352.48' TO A 1" IRON PIPE OF A 1984 SURVEY BY JOHN ORTH, SAID PIPE BEING THE POINT OF BEGINNING;
 THENCE N 89°23'49" W 212.00' ALONG THE SOUTH LINE OF SAID SURVEY;
 THENCE N 00°50'06" E 102.73';
 THENCE S 89°23'49" E 212.00';
 THENCE S 00°50'06" W 102.73' TO THE POINT OF BEGINNING CONTAINING 0.50 ACRES, MORE OR LESS, AND BEING SUBJECT TO ANY AND ALL EASEMENTS OF RECORD.

SURVEYOR'S CERTIFICATE: I, LARRY L. AUSTIN, REGISTERED WISCONSIN LAND SURVEYOR DO HEREBY CERTIFY THAT THE ABOVE SURVEY, DESCRIPTION, AND PLAT WERE PREPARED BY ME OR UNDER MY DIRECT SUPERVISION, IN ACCORDANCE WITH THE INSTRUCTIONS OF JERRY ROH, AND TO THE BEST OF MY KNOWLEDGE AND BELIEF, THIS PLAT IS AN ACCURATE REPRESENTATION THEREOF.

Larry L. Austin
 LARRY L. AUSTIN RLS 1903
 LARRY AUSTIN ENGINEERING
 RT.2
 LANCASTER, WI 53813
 PHONE (608) 723-6363



BEARING REFERENCE: FOR PURPOSES OF THIS SURVEY BEARING IS REFERENCED TO THE EAST LINE OF THE NE 1/4 OF SECTION 9, WHICH IS ASSUMED TO BEAR S 00°01'47"

LEGEND

- STONE MONUMENT FOUND
- 1" IRON PIPE FOUND
- 1" x 24" IRON PIPE SET
- () REC. DIM. OR BRGS.

