

SURVEY PLAT\*

OF A PARCEL OF LAND\* LOCATED IN W 1/2 OF SECTION 19, T 3 N, R 4 W OF THE 4TH P.M., GRANT COUNTY, WISCONSIN, MORE PARTICULARLY DESCRIBED AS FOLLOWS:

COMMENCING AT THE SOUTH 1/4 CORNER OF SECTION 19, T 3 N, R 4 W OF THE 4TH P.M., GRANT COUNTY, WISCONSIN; THENCE N 27°17'15" W 2622.99' TO A POINT ON THE NORTHERLY R.O.W. OF S.T.H. 133, SAID POINT BEING THE POINT OF BEGINNING;  
 THENCE N 01°10'15" W 374.76';  
 THENCE N 86°23'05" W 152.08';  
 THENCE S 00°46'16" E 359.17' TO THE NORTHERLY R.O.W. OF SAID S.T.H. 133;  
 THENCE S 80°45'52" E 156.63' ALONG SAID R.O.W. TO THE POINT OF BEGINNING, CONTAINING 1.288 ACRES, MORE OR LESS, AND BEING SUBJECT TO ANY AND ALL EASEMENTS OF RECORD.

SURVEYOR'S CERTIFICATE: I, LARRY L. AUSTIN, REGISTERED WISCONSIN LAND SURVEYOR, DO HEREBY CERTIFY THAT I HAVE SURVEYED, MAPPED AND MONUMENTED THAT PROPERTY SHOWN HEREON IN ACCORDANCE WITH THE INSTRUCTIONS OF PAT CLARE OF PLATTEVILLE, ATTORNEY FOR THE SEVENTH DAY ADVENTIST CHURCH, AND THAT THIS PLAT IS A CORRECT REPRESENTATION THEREOF, TO THE BEST OF MY KNOWLEDGE AND BELIEF.

*Larry L. Austin*  
 LARRY L. AUSTIN RLS 1903  
 LARRY AUSTIN ENGINEERING  
 RT 2  
 LANCASTER, WISCONSIN  
 PH (608) 723-6363

10/20/91  
 DATE  
 REVISED 12/30/94 AA

BEARING REFERENCE: FOR PURPOSES OF THIS SURVEY, BEARINGS ARE REFERENCED TO THE SOUTH LINE OF THE SE 1/4 OF SECTION 19, WHICH IS ASSUMED TO BEAR S 89°29'12" E.

\* NOTE: THIS SURVEY AND DESCRIPTION LOCATES THE EXISTING LINES OF OCCUPATION AS EVIDENCED BY FENCE LINES.

