

NF 83

3/169

CERTIFIED SURVEY MAP NO. _____ PAGE _____

FOR: Paul Moor
3604 CTH "H"
Kieler, WI 53812

BY: Blackhawk Engineering, Ltd.
2 Insight Dr.
Platteville, WI 53818

BOUNDARY DESCRIPTION

Parcel #1

A parcel of land located in the southwest 1/4 of the northwest 1/4 of Section 3, T 1 N, R 2 W, Jamestown Township, Grant County, Wisconsin, more fully described as follows:

Commencing at the southwest corner of the northwest 1/4 of said Section 3, thence N 1° 15' 15" E 701.89' along the west line of said northwest 1/4, thence S 90° 00' 00" E 1015.93' to the southwest corner of Certified Survey Map #343, thence S 84° 19' 54" E 94.70' along the south line of said Certified Survey Map #343 to the point of beginning, thence N 1° 59' 53" E 27.86' along said Certified Survey, thence S 87° 49' 19" E 219.49' along said Certified Survey to the east line of the SW 1/4 of the NW 1/4 of said Section 3, thence S 1° 01' 38" W 646.53' along the east line of the SW 1/4 of the NW 1/4 to the north right-of-way of County Trunk Highway "11", thence S 89° 40' 13" W 229.50' along said north right-of-way, thence N 1° 01' 38" E 468.35', thence N 4° 25' 41" E 160.44' to the point of beginning.

The above described parcel contains 3.408 acres, more or less, and is subject to any and all easements of record and/or usage.

SURVEYORS CERTIFICATE

I, Stanley J. King, Registered Land Surveyor, hereby certify in full compliance with Chapter 236.34 of the Wisconsin State Statutes and under the direction of Paul Moor, I have made a survey according to the description and instructions to furnished to me and that the certified survey drawn herein is a correct representation of that survey to the best of knowledge and belief.

Stanley King
Stanley J. King, FLS S-2001
Blackhawk Engineering, Ltd.
2 Insight Drive
Platteville, WI 53818
(608) 348-4433

10/6/00
Date



Certificate of Approval

CERTIFIED SURVEY MAP

No. _____ Page _____

LOCATED IN THE SOUTHWEST 1/4 OF THE NORTHWEST 1/4 OF SECTION 3,
TOWNSHIP 1 NORTH, RANGE 2 WEST,
JAMESTOWN TOWNSHIP, GRANT COUNTY, WISCONSIN

NW CORNER
SECTION 3
2" IP FOUND

- DENOTES 3/4" REBAR FOUND
- DENOTES 3/4" x 24" SOLID ROUND IRON ROD WEIGHING 1.50 LBS PER LINEAL FOOT SET.
- () DENOTES RECORDED AS BEARING
- 1) BEARINGS ARE REFERENCED TO THE WEST LINE OF THE SW 1/4 OF THE NW 1/4 OF SECTION 3, T1N, R2W. ASSUMED BEARING N 01°15'15" E.

