

# U.S. PUBLIC LAND SURVEY MONUMENT RECORD - GRANT COUNTY, WI

Section 2, Town 4 North Range 2 West, Town of Ellenboro (a)

NOTE: This form is intended and designed to fulfill all requirements of the Wisconsin Administrative Code Chapter A-E 7.08, U.S. Public Land Survey Monument Record (3) (a) (b) (c) (d) (e) (f) (g) (h) (i).

**CERTIFICATE: (i)**

I, Aaron J. Austin, Wisconsin Professional Land Surveyor, do hereby certify that the corner location on this record was determined by me and/or under my direct supervision and that this U.S. Public Land Survey Monument Record is correct and complete to the best of my knowledge and belief.

Dated this 28th day of August, 2025.

*Aaron J. Austin*  
Aaron J. Austin, PLS-2922



⊕ = CORNER LOCATION

Grant County Coordinates:  
NAD 83 (2011)  
Northing: 524,237.25  
Easting: 857,691.68

**HISTORY OF CORNER ESTABLISHMENT:**

Original corner was set in 1833 by Robert Clark.  
Joel Barber found the Original Corner on a Survey filed in Book B, Page 521 dated 3-13-1868.  
Joel Barber found the Original Corner on a Survey filed in Book D, Page 15 dated 4-16-1877.

**DESCRIPTION OF CORNER EVIDENCE FOUND: (b) (f) (g) (h)**

I set a 1" x 24" Rebar at the recorded distance from an original bearing tree which matched well with an occupied East-West fence at the South line of the NE 1/4, SE 1/4 of Section 2. I set four witness corners after I verified the Monument's location with G.P.S. and E.D.M. methods.

**DESCRIPTION OF CORNER AND WITNESS MONUMENTS, references and accessories used to perpetuate the original or re-established location of this corner. (c) (d) (e)**

Witnesses to corner location Shane Austin, Owen Austin, Tanner Austin.  
Drawn by: Owen Austin.

SKETCH:

## LEGEND

- ⊕ Section Corner—as designated
- 3/4" x 18" rebar set
- ⊙ Existing tree
- x-x-x- Existing fence

FIELD

PASTURE

PASTURE

EAST 1/4 CORNER  
SECTION 2, T4N R2W  
1" x 24" Rebar set.

Occupied South line  
of the NE 1/4, SE 1/4  
of Section 2.

Bearing tree

