

GRANT COUNTY CERTIFIED LAND CORNER


CORNER NUMBER 81

CERTIFICATE:

I, Larry L. Austin, do hereby certify that on the 13th day of October, 2000, I found evidence of the Southeast corner of Section 24, Town 4 North, Range 1 West, of the 4th Principal Meridian, and I re-established said corner according to the Wisconsin statutes as shown and described hereon.

Dated this 13th day of November, 2000

Larry L. Austin
Larry L. Austin S-1903



● = CORNER LOCATION

SOUTHEAST CORNER OF SECTION 24, T 4 N R 1 W TOWN OF LIMA

HISTORY OF ORIGINAL CORNER ESTABLISHMENT:

Corner was originally set in 1832 by Sibley.
In 1992 Bruce Bowden located an existing 2" iron pipe in concrete.

DESCRIPTION OF CORNER EVIDENCE FOUND:

I located the existing 2" iron pipe in concrete and accepted it's location after an EDM & GPS traverse of the area.

DESCRIPTION OF CORNER AND WITNESS MONUMENTS, references and accessories used to perpetuate the original or re-established location of this corner

WITNESS TO THE CORNER LOCATION: SHANE AUSTIN & SHELBY BLINDERT & BOBBY SEDGWICK

SKETCH:



FIELDS

ROAD

PASTURE

N 87°06'23" W 13.40'

N 01°35'27" E 38.62'

19

N 88°11'21" E 31.47'

24

FIELD

S 00°54'23" E 29.30'

30

FIELDS

FIELDS

LEGEND

- 2" pipe post in concrete found
- Number 4 by 24" rebar set with red plastic cap
- x— Existing fence location